



SEDIMENT CONTROL



- CONSTRUCTION NOTES**
- CONSTRUCT SEDIMENT FENCES AS CLOSE AS POSSIBLE TO BEING PARALLEL TO THE CONTOURS OF THE SITE, BUT WITH SMALL RETURNS AS SHOWN IN THE DRAWING TO LIMIT THE CATCHMENT AREA OF ANY ONE SECTION. THE CATCHMENT AREA SHOULD BE SMALL ENOUGH TO LIMIT WATER FLOW IF CONCENTRATED AT ONE POINT TO 50 LITRES PER SECOND IN THE DESIGN STORM EVENT, USUALLY THE 10-YEAR EVENT.
 - CUT A 150-MM DEEP TRENCH ALONG THE UPSLOPE LINE OF THE FENCE FOR THE BOTTOM OF THE FABRIC TO BE ENTRENCHED.
 - DRIVE 1.5 METRE LONG STAR PICKETS INTO GROUND AT 2.5 METRE INTERVALS (MAX) AT THE DOWNSLOPE EDGE OF THE TRENCH. ENSURE ANY STAR PICKETS ARE FITTED WITH SAFETY CAPS.
 - FIX SELF-SUPPORTING GEOTEXTILE TO THE UPSLOPE SIDE OF THE TRENCH. FIX THE GEOTEXTILE WITH WIRE TIES OR AS RECOMMENDED BY THE MANUFACTURER. ONLY USE GEOTEXTILE SPECIFICALLY PRODUCED FOR SEDIMENT FENCING. THE USE OF SHADE CLOTH FOR THIS PURPOSE IS NOT SATISFACTORY.
 - JOIN SECTIONS OF FABRIC AT A SUPPORT POST WITH A 150-MM OVERLAP.
 - BACKFILL THE TRENCH OVER THE BASE OF THE FABRIC AND COMPACT IT THOROUGHLY OVER THE GEOTEXTILE.



- CONSTRUCTION NOTES**
- INSTALL FILTERS TO KERB INLETS ONLY AT SAG POINTS.
 - FABRICATE A SLEEVE MADE FROM GEOTEXTILE OR WIRE MESH LONGER THAN THE LENGTH OF THE INLET PIT AND FILL IT WITH 25 MM TO 50 MM GRAVEL.
 - FORM AN ELLIPTICAL CROSS-SECTION ABOUT 150 MM HIGH X 400 MM WIDE.
 - PLACE THE FILTER AT THE OPENING LEAVING AT LEAST A 100-MM SPACE BETWEEN IT AND THE KERB INLET. MAINTAIN THE OPENING WITH SPACER BLOCKS.
 - FORM A SEAL WITH THE KERB TO PREVENT SEDIMENT BYPASSING THE FILTER.
 - SANDBAGS FILLED WITH GRAVEL CAN SUBSTITUTE FOR THE MESH OR GEOTEXTILE PROVIDING THEY ARE PLACED SO THAT THEY FIRMLY ABUT EACH OTHER AND SEDIMENT-LADEN WATERS CANNOT PASS BETWEEN.

SITE NOTES

- CONFIRM ALL DIMENSIONS ON SITE TO EXISTING RESIDENCE PRIOR TO COMMENCEMENT OF ANY WORK.
- THIS PLAN DOES NOT PROVIDE SPECIFIC LANDSCAPE PLANTING LOCATIONS.
- THE EXACT LOCATION OF UNDERGROUND AND ABOVEGROUND SERVICES SHALL BE PROVEN ON SITE. NO GUARANTEE IS GIVEN THAT ALL EXISTING SERVICES ARE SHOWN.
- THIS DRAWING SET TO BE READ IN CONJUNCTION WITH THE SPECIFICATION PROVIDED.
- BEWARE OF EXISTING SERVICES. CONFIRM LOCATIONS PRIOR TO EXCAVATION. TAKE EXTREME CARE.

LEGEND

- TEMPORARY SITE MATERIAL DISPOSAL ARE DURING CONSTRUCTION. TO BE PROTECTED BY A SEDIMENT FENCE OR STRAW BALE FILTER.
- SITE ACCESS DURING CONSTRUCTION.

SITE COVERAGE

LOT G13 KNOX CRESCENT, CAERLEON	= 986.20M ²
SITE COVERAGE	= 336.52M ²
TOTAL GFA EXCLUDING PORCH # ALFRESCO AREAS	= 34.12%

SUBDIVISION NOTES

LOT G13 KNOX CRESCENT CAERLEON DP 1272616 - ZONING R1 GENERAL RESIDENTIAL	
TOTAL LOT G13 AREA	= 986.20M ²
PROPOSED LOT 1 (DWELLING ONE)	= 493.10M ²
PROPOSED LOT 2 (DWELLING TWO)	= 493.10M ²


- CONFIRM ALL DIMENSIONS BACK TO SPECIFIC SURVEY PLANS PRIOR TO COMMENCEMENT OF ANY WORK.
- PROPOSED DIVIDING SUBDIVISION BOUNDARY IS APPROXIMATE ONLY AND TO BE CONFIRMED AS ABOVE.
- PROPOSED LOT AREAS ARE APPROXIMATE ONLY & SHOULD BE READ IN CONJUNCTION WITH SPECIFIC SURVEY PLANS.

LANDSCAPING DETAILS

- SMALL SHRUBS TO 1.0M HIGH**
- SURFER BOY (PHORMIUM)
 - BRONZE BABY (PHORIUM)
 - GOLF BABY (PITTOSPORIUM)
- SMALL ORNAMENTAL TREES TO 3.0M HIGH**
- MANCHURIAN PEAR (PYRUS USSURIENSIS)


CONSULT LOCAL NURSERY FOR AVAILABILITY AND SUITABILITY OF THE SPECIES LISTED & SUBSTITUTE SIMILAR PLANTING IF REQUIRED. MULCH BEDS WITH WOODCHIP OR PEBBLES & FILL OUT OR LINE BEDS WITH GROUND COVERS OR SIMILAR SMALL PLANTS. EDGE BEDS WITH INSITU FORMED CONCRETE ROLLED EDGE, SLEEPERS, MASCONARY BLOCK EDGING OR SIMILAR AS SELECTED.

KIKUYU TURF TO ALL AREAS, UNLESS GRAVEL IS STATED AND DISPLAYED OTHERWISE.



LOCATION PLAN

SCALE: NTS



SITE, SUBDIVISION & LANDSCAPING PLAN

SCALE: 1:200

THIS DRAWING IS SUBJECT TO COPYRIGHT & MUST NOT BE REPRODUCED OR USED FOR MEANS OTHER THAN INTENDED WITHOUT THE WRITTEN PERMISSION OF THE AUTHOR - LYNCH BUILDING GROUP

REV	DATE	DESCRIPTION
A	25/05/2021	INITIAL CONCEPT PRESENTED
B	15/07/2021	CONTRACT PLANS FOR REVIEW
C	2/11/2022	PRELIMINARY CONTRACT PLANS
D	08/02/2023	FINAL PCA SUBMISSION PLANS

NOTE:
ALL DRAWINGS TO BE READ IN CONJUNCTION WITH -
- ALL SHEETS TO THIS SET OF PLANS
- SEPERATE SPECIFICATION DOCUMENTS
- STRUCTURAL ENGINEERS DOCUMENTATION
- PCA DOCUMENTS (WHERE APPLICABLE)
- BASIX CERTIFICATE
- ALL RELEVANT CODES, STANDARDS & APPROVALS






LYNCH BUILDING GROUP
BEER PROJECT
CLIENT:
PROPOSED DETACHED DUAL OCCUPANCY
LOT G13 KNOX CRESCENT
CAERLEON NSW 2850
PROJECT:



LYNCH BUILDING GROUP



LOCATION, SITE, SUBDIVISION & LANDSCAPING PLAN			
DRAWING TITLE:			
DESIGN: LBG	FILE NO: 0446-A01	02 OF 09	D
DRAFTED: J.LYNCH	PAPER SIZE: A3	DRAWING NO:	REV:
CHECKED: A.LYNCH			



FLOOR PLAN - DWELLING ONE

SCALE: 1:100

FLOOR AREAS

DWELLING ONE	
- LIVING	= 146.10 M ²
- GARAGE	= 22.31 M ²
TOTAL	= 168.41 M²
<hr/>	
- PORCH	= 1.60 M ²
- ALFRESCO	= 10.64 M ²
TOTAL DWELLING ONE	= 180.65 M²

NOTES

- PORCH # ALFRESCO POST POSITION(S)
MAY VARY THROUGH ENGINEERS DESIGNS #
DURING CONSTRUCTION.
- ☐ MH = MAN HOLE LOCATION
- ALL OPENINGS ARE SHOWN WITH WIDTH DISPLAYED
ON FLOOR PLAN. HEAD HEIGHTS SHALL BE NO LESS
THAN 2.2M FROM F.F.L. UNLESS STATED OTHERWISE

THIS DRAWING IS SUBJECT TO COPYRIGHT # MUST NOT BE REPRODUCED OR USED FOR MEANS OTHER THAN INTENDED WITHOUT THE WRITTEN PERMISSION OF THE AUTHOR - LYNCH BUILDING GROUP

REV	DATE	DESCRIPTION
A	25/05/2021	INITIAL CONCEPT PRESENTED
B	15/07/2021	CONTRACT PLANS FOR REVIEW
C	21/10/2022	PRELIMINARY CONTRACT PLANS
D	08/02/2023	FINAL PCA SUBMISSION PLANS

NOTE:
 - ALL DRAWINGS TO BE READ IN CONJUNCTION WITH -
 - ALL SHEETS TO THIS SET OF PLANS
 - SEPARATE SPECIFICATION DOCUMENTS
 - STRUCTURAL ENGINEERS DOCUMENTATION
 - PCA DOCUMENTS (WHERE APPLICABLE)
 - BASIX CERTIFICATE
 - ALL RELEVANT CODES, STANDARDS # APPROVALS







LYNCH BUILDING GROUP
 BEER PROJECT
 CLIENT:
 PROPOSED DETACHED DUAL OCCUPANCY
 LOT 613 KNOX CRESCENT
 CAERLEON NSW 2850
 PROJECT:



LYNCH BUILDING GROUP

FLOOR PLAN - DWELLING ONE

DRAWING TITLE:	DESIGN: LBG	FILE NO: 0446-A01	03 OF 09	D
DRAFTED: J.LYNCH	CHECKED: A.LYNCH	PAPER SIZE: A3	DRAWING NO:	REV:



FLOOR PLAN - DWELLING TWO

SCALE: 1:100

FLOOR AREAS	
DWELLING TWO	
- LIVING	= 146.10 M ²
- GARAGE	= 22.31 M ²
TOTAL	= 168.41 M²
- PORCH	= 3.51 M ²
- ALFRESCO	= 10.64 M ²
TOTAL DWELLING TWO	= 182.56 M²

NOTES	
■	PORCH & ALFRESCO POST POSITION(S) MAY VARY THROUGH ENGINEERS DESIGNS & DURING CONSTRUCTION.
□	MH = MAN HOLE LOCATION
----	ALL OPENINGS ARE SHOWN WITH WIDTH DISPLAYED ON FLOOR PLAN. HEAD HEIGHTS SHALL BE NO LESS THAN 2.2M FROM F.F.L. UNLESS STATED OTHERWISE

THIS DRAWING IS SUBJECT TO COPYRIGHT & MUST NOT BE REPRODUCED OR USED FOR MEANS OTHER THAN INTENDED WITHOUT THE WRITTEN PERMISSION OF THE AUTHOR - LYNCH BUILDING GROUP

REV	DATE	DESCRIPTION
A	25/05/2021	INITIAL CONCEPT PRESENTED
B	15/07/2021	CONTRACT PLANS FOR REVIEW
C	21/10/2022	PRELIMINARY CONTRACT PLANS
D	08/02/2023	FINAL PCA SUBMISSION PLANS

NOTE:
 - ALL DRAWINGS TO BE READ IN CONJUNCTION WITH -
 - ALL SHEETS TO THIS SET OF PLANS
 - SEPARATE SPECIFICATION DOCUMENTS
 - STRUCTURAL ENGINEERS DOCUMENTATION
 - PCA DOCUMENTS (WHERE APPLICABLE)
 - BASIX CERTIFICATE
 - ALL RELEVANT CODES, STANDARDS & APPROVALS



LYNCH BUILDING GROUP
 BEER PROJECT
 CLIENT:
 PROPOSED DETACHED DUAL OCCUPANCY
 LOT 613 KNOX CRESCENT
 CAERLEON NSW 2850
 PROJECT:




LYNCH BUILDING GROUP



FLOOR PLAN - DWELLING TWO

DRAWING TITLE:			
DESIGN: LBG	FILE NO: 0446-A01	04 OF 09	D
DRAFTED: J.LYNCH	PAPER SIZE: A3	DRAWING NO:	REV:
CHECKED: A.LYNCH			

DWELLING ONE




WEST ELEVATION

SCALE: 1:100

SOUTH ELEVATION

SCALE: 1:100



EAST ELEVATION

SCALE: 1:100

NORTH ELEVATION

SCALE: 1:100

THIS DRAWING IS SUBJECT TO COPYRIGHT & MUST NOT BE REPRODUCED OR USED FOR MEANS OTHER THAN INTENDED WITHOUT THE WRITTEN PERMISSION OF THE AUTHOR - LYNCH BUILDING GROUP

REV	DATE	DESCRIPTION
A	25/05/2021	INITIAL CONCEPT PRESENTED
B	15/07/2021	CONTRACT PLANS FOR REVIEW
C	21/10/2022	PRELIMINARY CONTRACT PLANS
D	08/02/2023	FINAL PCA SUBMISSION PLANS

NOTE:
 ALL DRAWINGS TO BE READ IN CONJUNCTION WITH -
 - ALL SHEETS TO THIS SET OF PLANS
 - SEPERATE SPECIFICATION DOCUMENTS
 - STRUCTURAL ENGINEERS DOCUMENTATION
 - PCA DOCUMENTS (WHERE APPLICABLE)
 - BASIX CERTIFICATE
 - ALL RELEVANT CODES, STANDARDS & APPROVALS



LYNCH BUILDING GROUP
 BEER PROJECT
 CLIENT:
 PROPOSED DETACHED DUAL OCCUPANCY
 LOT 613 KNOX CRESCENT
 CAERLEON NSW 2850
 PROJECT:




LYNCH BUILDING GROUP



ELEVATIONS - DWELLING ONE

DRAWING TITLE:			
DESIGN: LBG	FILE NO: 044G-A01	05 OF 09	D
DRAFTED: J.LYNCH	PAPER SIZE: A3	DRAWING NO:	REV:
CHECKED: A.LYNCH			

DWELLING TWO




WEST ELEVATION

SCALE: 1:100

SOUTH ELEVATION

SCALE: 1:100



EAST ELEVATION

SCALE: 1:100

NORTH ELEVATION

SCALE: 1:100

THIS DRAWING IS SUBJECT TO COPYRIGHT & MUST NOT BE REPRODUCED OR USED FOR MEANS OTHER THAN INTENDED WITHOUT THE WRITTEN PERMISSION OF THE AUTHOR - LYNCH BUILDING GROUP

REV	DATE	DESCRIPTION
A	25/05/2021	INITIAL CONCEPT PRESENTED
B	15/07/2021	CONTRACT PLANS FOR REVIEW
C	21/10/2022	PRELIMINARY CONTRACT PLANS
D	08/02/2023	FINAL PCA SUBMISSION PLANS

NOTE:
 ALL DRAWINGS TO BE READ IN CONJUNCTION WITH -
 - ALL SHEETS TO THIS SET OF PLANS
 - SEPERATE SPECIFICATION DOCUMENTS
 - STRUCTURAL ENGINEERS DOCUMENTATION
 - PCA DOCUMENTS (WHERE APPLICABLE)
 - BASIX CERTIFICATE
 - ALL RELEVANT CODES, STANDARDS & APPROVALS



LYNCH BUILDING GROUP
 BEER PROJECT
 CLIENT:
 PROPOSED DETACHED DUAL OCCUPANCY
 LOT 613 KNOX CRESCENT
 CAERLEON NSW 2850
 PROJECT:




LYNCH BUILDING GROUP



ELEVATIONS - DWELLING TWO

DRAWING TITLE:			
DESIGN:	LBG	FILE NO:	0446-A01
DRAFTED:	J.LYNCH		
CHECKED:	A.LYNCH	PAPER SIZE:	A3
		DRAWING NO:	06 OF 09
		REV:	D



TYPICAL SECTION

SCALE: 1:50

SECTION NOTES

- 1| FOR COMPLETE SLAB DETAILS & DESIGN REFER TO ENGINEERS SPECIFICATIONS & DESIGNS.
- 2| TERMITE TREATMENT SHALL BE INCLUDED TO PROTECT AGAINST INFESTATION TO AS3660.1-2000
- 3| PARTY WALL DETAILS -
 - SEPARATING PARTY WALL MUST NOT BE CROSSED BY TIMBER OR OTHER COMBUSTIBLE BUILDING ELEMENTS WITH THE EXCEPTION OF STEEL ROOFING BATTENS WITH DIMENSIONS 75x50MM OR ROOF SARKING, MUST ALSO BE PACKED USING FIRE RESISTANT MATERIAL IN ACCORDANCE WITH THE B.C.A.
 - 25MM GYPROCK SHAFT LINER PANEL BETWEEN STEEL "H" WITH 20-40MM OF SEPERATION BETWEEN FRAMES & GYPROCK SHAFT LINER PANEL.
 - STUDS AT 600MM MAXIMUM CENTRES
 - 10MM GYPROCK "SUPERCHEK" PLASTERBOARD WALL LINING TO FACE OF PARTY WALL (GYPROCK EWFA 45743 CSR 360 PARTY WALL SYSTEM)
 - SELECT WALL FRAMING WITH R2.7 GOLD WALL INSULATION BATTs TO BE INSTALLED.
 - FIRE RESISTANT MINERAL FIRE BLANKET TO BE INSTALLED DIRECTLY ABOVE PARTY WALL TO UNDERSIDE OF ROOFING IN ACCORDANCE WITH THE B.C.A.

GENERAL NOTES

- | | | | |
|--|---|---|--|
| <ol style="list-style-type: none"> 1 PLANS DOCUMENTED FOR THE EXCLUSIVE USE OF THE NOTED CLIENTS BELOW ONLY & SUBJECT TO COPYRIGHT LAWS. 2 ALL DIMENSIONS & INFORMATION WITHIN THESE SET OF PLANS ARE DOCUMENTED WITH DUE CARE. 3 ALL DRAWINGS WITHIN THIS SET OF PLANS SHALL BE READ IN CONJUNCTION WITH OTHER CONSULTANTS DRAWINGS, DESIGNS & SPECIFICATIONS & WITH OTHER WRITTEN INSTRUCTIONS ISSUED DURING ESTIMATIONS & CONSTRUCTION WITH SELECTED BUILDER. 4 ALL DISCREPANCIES SHALL BE REFERRED TO, IN WRITING TO, JHL BUILDING DESIGNS FOR A DECISION BEFORE PROCEEDING WITH THE WORK. 5 ALL DIMENSIONS ARE IN MILLIMETRES UNLESS STATED OTHERWISE. DIMENSIONS ARE TO STRUCTURAL ELEMENTS OF THE DRAWING & NOT TO FINISHED SURFACES IE. TILING, PLASTERBOARD ETC. 6 ALL RELEVANT DIMENSIONS ARE TO BE CONFIRMED BY THE CONTRACTOR PRIOR TO CONSTRUCTION & FABRICATION WITH REGARDS TO ONSITE & OFF SITE REQUIREMENTS & WORK. | <ol style="list-style-type: none"> 7 THE RELEVANT SERVICE AUTHORITIES SHALL BE CONSULTED IN REGARDS TO CONFIRMING / CHECKING ALL DIMENSIONS, LEVELS, SERVICES & SITE CONDITIONS PRIOR TO CONSTRUCTION. 8 THE RELEVANT STATUTORY AUTHORITIES SHALL BE NOTIFIED & APPROVAL SORT FROM / OBTAINED PRIOR TO CONSTRUCTION, IF & WHEN NECESSARY. 9 STUD WALL & TRUSSED ROOF DESIGN, BRACING & TIE DOWN TO SELECTED FRAME & TRUSS MANUFACTURERS ENGINEERED SPECIFICATIONS & TO AS 1684 WHERE APPLICABLE. 10 SHALL NO WIND CLASSIFICATION BE NOTED, CLIENT TO BE ADVISED BY PCA OR ENGINEERING CONSULTANT. 11 SITE CLASSIFICATION TO BE DETERMINED BY QUALIFIED GEOTECHNICAL ENGINEER & ALL REINFORCED CONCRETE FOOTINGS & SLABS TO BE CONSTRUCTED TO AS2870. 12 ALL STORM WATER FROM ROOF TO BE DISPURSED TO REQUIRED DOWNPIPES & TO STREET / RAIN WATER TANK TO AUSTRALIAN STANDARDS & PCA REQUIREMENTS. | <ol style="list-style-type: none"> 13 A MINIMUM WATER ALLOWANCE SHALL BE PROVIDED FOR RURAL PROPERTIES FOR FIRE FIGHTING PURPOSES AS SPECIFIED BY PCA. 14 WHERE A SITE REQUIRES CUT & FILL TO OCCUR OR RETAINING WALLS CONSTRUCTED, ENGINEERS SHALL BE CONSULTED WHERE NECESSARY & BUILDING CONTRACTOR TO ENSURE ALL FINAL LEVELS, GROUND LINES & GRADIENTS DIVERT ALL SURFACE STORM WATER FROM THE PROPOSED RESIDENCE EITHER BY MEANS OF PIPES, DETENTION AREAS OR GRADING TO KERB. NEIGHBOURING PROPERTIES MUST BE TAKEN INTO CONSIDERATION WITH THE DESIGN OF THE FLOW OF STORM WATER. 15 SEWER DRAINAGE LINES TO BE CONNECTED TO SEWER MAIN OR IN THE CASE OF A RURAL PROPERTY, CONNECTED TO A SEPTIC SYSTEM, IN ACCORDANCE WITH THE RELEVANT AUSTRALIAN STANDARDS & LOCAL PCA. 16 A QUALIFIED CONTRACTOR SHALL COMPLETE THE FINAL DRAINAGE LAYOUT TO BE SUBMITTED TO THE LOCAL PCA FOR THEIR RECORDS & APPROVAL. | <ol style="list-style-type: none"> 17 THE HOT WATER SYSTEM IS AS SPECIFIED WITHIN THE BASIX CERTIFICATE & LOCATION NOTED OF FLOOR PLAN. 18 TERMITE PROTECTION SHALL BE IN ACCORDANCE WITH AS3660. 19 WHERE BRICK VENEER CONSTRUCTION IS SPECIFIED, CONTROL JOINTS FOR ARTICULATION MUST BE PROVIDED AT NOMINAL 6.0M MAX. CENTRES OR TO STRUCTURAL ENGINEERS DETAILS. |
|--|---|---|--|

THIS DRAWING IS SUBJECT TO COPYRIGHT & MUST NOT BE REPRODUCED OR USED FOR MEANS OTHER THAN INTENDED WITHOUT THE WRITTEN PERMISSION OF THE AUTHOR - LYNCH BUILDING GROUP

REV	DATE	DESCRIPTION
A	25/05/2021	INITIAL CONCEPT PRESENTED
B	15/07/2021	CONTRACT PLANS FOR REVIEW
C	21/10/2022	PRELIMINARY CONTRACT PLANS
D	08/02/2023	FINAL PCA SUBMISSION PLANS



LYNCH BUILDING GROUP
BEER PROJECT
CLIENT:
PROPOSED DETACHED DUAL OCCUPANCY
LOT 613 KNOX CRESCENT
CAERLEON NSW 2850
PROJECT:



LYNCH BUILDING
GROUP


TYPICAL SECTION

DRAWING TITLE:

07 OF 09 D


REV:

DWELLING ONE



ELECTRICAL PLAN

SCALE: NTS



MECHANICAL PLAN

SCALE: NTS

LEGEND

X 300	SINGLE POWER POINT (DISTANCE ABOVE F.F.L.)	(4)
XX 300	DOUBLE POWER POINT (DISTANCE ABOVE F.F.L.)	(15)
—	FLUORESCENT LIGHTS - SINGLE	(1)
○	DOWN LIGHT	(23)
□	EXTERNAL WALL LIGHT	(-)
⊗	SENSOR LIGHT	(1)
⊗	STANDARD BATTEN	(7)
⊗	TASTIC LIGHT - 4 LIGHT	(1)
⊗	TASTIC LIGHT - 2 LIGHT	(1)
TV	TELEVISION OUTLET	(2)
PH	NBN POINT LOCATION	(1)
—	2-WAY SWITCH	(-)
P	PENDANT LIGHT	(-)
XX	EXTERNAL DOUBLE POWER POINT	(2)
⊗	CEILING FAN - WITH LIGHT	(1)

ELECTRICAL NOTES

- 1 | ALL ELECTRICAL WORK SHALL BE CARRIED OUT BY A LICENSED CONTRACTOR. ALL WORK SHALL BE IN ACCORDANCE WITH AS/NZ3012 & ALL LINENSING REQUIREMENTS.
- 2 | THE SELECTION OF FITTINGS AND THE LAYOUT TO BE CARRIED OUT BY THE BUILDER & DESIGNED TO THE CLIENT'S REQUIREMENTS.
- 3 | ALL APPROVED SMOKE ALARMS / DETECTORS TO BE INSTALLED TO AS3786 BY A LICENSED CONTRACTOR.

LEGEND

□	OUTDOOR AIR CONDITIONER UNIT
■	ZONES
●	SUPPLY AIR GRILLS
□	RETURN AIR GRILLS
■	AIR CONDITIONER UNIT IN ROOF SPACE
—	AIR CONDITIONER CONTROL PANEL
■	INDOOR WALL MOUNTED SPLIT SYSTEM

MECHANICAL NOTES

- 1 | ALL MECHANICAL WORKS REGARDING AIR CONDITIONING SHALL BE CARRIED OUT BY A LICENSED CONTRACTOR. ALL WORK SHALL BE IN ACCORDANCE WITH AS STANDARDS & ALL LINENSING REQUIREMENTS.
- 2 | THE SELECTION OF FITTINGS AND THE LAYOUT TO BE CONFIRMED BY THE BUILDER & DESIGNED TO THE CLIENT'S REQUIREMENTS.
- 3 | GENERAL LAYOUT OF SUPPLY AIR GRILLS ETC IS TO BE VIEWED AS AN EXAMPLE ONLY & CAN CHANGE THROUGHOUT INSTALLATION

THIS DRAWING IS SUBJECT TO COPYRIGHT & MUST NOT BE REPRODUCED OR USED FOR MEANS OTHER THAN INTENDED WITHOUT THE WRITTEN PERMISSION OF THE AUTHOR - LYNCH BUILDING GROUP

REV	DATE	DESCRIPTION
A	25/05/2021	INITIAL CONCEPT PRESENTED
B	15/07/2021	CONTRACT PLANS FOR REVIEW
C	21/10/2022	PRELIMINARY CONTRACT PLANS
D	08/02/2023	FINAL PCA SUBMISSION PLANS

NOTE:
ALL DRAWINGS TO BE READ IN CONJUNCTION WITH -
- ALL SHEETS TO THIS SET OF PLANS
- SEPERATE SPECIFICATION DOCUMENTS
- STRUCTURAL ENGINEERS DOCUMENTATION
- PCA DOCUMENTS (WHERE APPLICABLE)
- BASIX CERTIFICATE
- ALL RELEVANT CODES, STANDARDS & APPROVALS



LYNCH BUILDING GROUP
BEER PROJECT
CLIENT:
PROPOSED DETACHED DUAL OCCUPANCY
LOT 613 KNOX CRESCENT
CAERLEON NSW 2850
PROJECT:




LYNCH BUILDING GROUP



ELECTRICAL & MECHANICAL PLANS - DWELLING ONE
DRAWING TITLE:


DESIGN:	LBG	FILE NO:	0446-A01	08 OF 09	D
DRAFTED:	J.LYNCH	PAPER SIZE:	A3	DRAWING NO:	REV:

DWELLING TWO



ELECTRICAL PLAN

SCALE: NTS



MECHANICAL PLAN

SCALE: NTS

LEGEND

X 300	SINGLE POWER POINT (DISTANCE ABOVE F.F.L.)	(4)
XX 300	DOUBLE POWER POINT (DISTANCE ABOVE F.F.L.)	(15)
—	FLUORESCENT LIGHTS - SINGLE	(1)
○	DOWN LIGHT	(23)
□	EXTERNAL WALL LIGHT	(-)
⊗	SENSOR LIGHT	(1)
⊗	STANDARD BATTEN	(7)
⊗	TASTIC LIGHT - 4 LIGHT	(1)
⊗	TASTIC LIGHT - 2 LIGHT	(1)
TV	TELEVISION OUTLET	(2)
PH	TELEPHONE	(1)
—	2-WAY SWITCH	(-)
P	PENDANT LIGHT	(-)
OX	EXTERNAL DOUBLE POWER POINT	(2)
⊗	CEILING FAN - WITH LIGHT	(1)

ELECTRICAL NOTES

- ALL ELECTRICAL WORK SHALL BE CARRIED OUT BY A LICENSED CONTRACTOR. ALL WORK SHALL BE IN ACCORDANCE WITH AS/NZ3012 & ALL LINENSING REQUIREMENTS.
- THE SELECTION OF FITTINGS AND THE LAYOUT TO BE CARRIED OUT BY THE BUILDER & DESIGNED TO THE CLIENT'S REQUIREMENTS.
- ALL APPROVED SMOKE ALARMS / DETECTORS TO BE INSTALLED TO AS3786 BY A LICENSED CONTRACTOR.

LEGEND

□	OUTDOOR AIR CONDITIONER UNIT
■	ZONES
●	SUPPLY AIR GRILLS
□	RETURN AIR GRILLS
■	AIR CONDITIONER UNIT IN ROOF SPACE
—	AIR CONDITIONER CONTROL PANEL
■	INDOOR WALL MOUNTED SPLIT SYSTEM

MECHANICAL NOTES

- ALL MECHANICAL WORKS REGARDING AIR CONDITIONING SHALL BE CARRIED OUT BY A LICENSED CONTRACTOR. ALL WORK SHALL BE IN ACCORDANCE WITH AS STANDARDS & ALL LINENSING REQUIREMENTS.
- THE SELECTION OF FITTINGS AND THE LAYOUT TO BE CONFIRMED BY THE BUILDER & DESIGNED TO THE CLIENT'S REQUIREMENTS.

THIS DRAWING IS SUBJECT TO COPYRIGHT & MUST NOT BE REPRODUCED OR USED FOR MEANS OTHER THAN INTENDED WITHOUT THE WRITTEN PERMISSION OF THE AUTHOR - LYNCH BUILDING GROUP

REV	DATE	DESCRIPTION
A	25/05/2021	INITIAL CONCEPT PRESENTED
B	15/07/2021	CONTRACT PLANS FOR REVIEW
C	21/10/2022	PRELIMINARY CONTRACT PLANS
D	08/02/2023	FINAL PCA SUBMISSION PLANS

NOTE:
ALL DRAWINGS TO BE READ IN CONJUNCTION WITH -
- ALL SHEETS TO THIS SET OF PLANS
- SEPERATE SPECIFICATION DOCUMENTS
- STRUCTURAL ENGINEERS DOCUMENTATION
- PCA DOCUMENTS (WHERE APPLICABLE)
- BASIX CERTIFICATE
- ALL RELEVANT CODES, STANDARDS & APPROVALS



LYNCH BUILDING GROUP
BEER PROJECT
CLIENT:
PROPOSED DETACHED DUAL OCCUPANCY
LOT 613 KNOX CRESCENT
CAERLEON NSW 2850
PROJECT:



ELECTRICAL & MECHANICAL PLANS - DWELLING TWO			
DRAWING TITLE:			
DESIGN:	LBG	FILE NO:	0446-A01
DRAFTED:	J.LYNCH		
CHECKED:	A.LYNCH	PAPER SIZE:	A3
		DRAWING NO:	09 OF 09
		REV:	D